INSTALLATION INSTRUCTIONS

Building a Deck Project

JANUARY 1, 2026

MY HOME HARDWARE CO.
1234 Cree Cir NE, Hartville, OH 44632-9465

Table of Contents

1. Introduction 2
2. Foundation and Structural Work 3
3. Deck Framing and Surface Preparation 4
4. Stair Construction and Installation 6
5. Railing and Safety Barrier Installation 8

1. Introduction

About this Guide

This manual provides a comprehensive, step-by-step guide to building a residential outdoor deck. The project is organized into four key phases:

1. Foundation and Structural Work
2. Deck Framing and Surface Preparation
3. Stair Construction and Installation
4. Railing and Safety Barrier Installation

Each section includes detailed instructions, a list of required tools and materials, and clear illustrations to guide you through the process. Whether you are repairing an existing deck or constructing a new one, this manual is designed to make the task straightforward and achievable.

By following the recommended sequence of steps, you will ensure safety, efficiency, and a professional-quality finish. Take your time, review each phase carefully, and enjoy the satisfaction of completing your own outdoor deck project.

Before You Begin

A. Introduction

Before starting your deck project, take the following steps to ensure safety, compliance, and efficiency:

1. **Plan Your Deck**
   Determine the size, layout, and intended purpose of the deck.

2. **Check Utility Locations**
   Confirm the location of underground utilities prior to any excavation to prevent damage and ensure safety.

3. **Review Instructions Thoroughly**
   Read this manual carefully to familiarize yourself with the required tools, materials, and the sequence of steps for each phase of the project.

4. **Follow Guidelines Precisely**
   Adhere strictly to the instructions provided to avoid costly mistakes and ensure a professional quality result.

B. Installer Hazard Information

⚠ **CAUTION!!** Risk of personal injury.
Some tools are very heavy, and some materials need careful handling. For your protection, wear appropriate safety equipment when working with these products.

Prior to Construction

Before starting the deck installation, complete the following checks and preparations

1. **Site Preparation**
   - Clear all vegetation, debris, and obstacles from the work area.

- Mark the deck layout using stakes and string lines, ensuring accuracy against your design plan.
- Verify footing placement, post spacing, stair requirements, and railing height in accordance with local building codes.

2. **Tools and Material Inspection**
   - Inspect all tools and materials for damage that may have occurred during shipping or storage.
   - After inspection, keep tools and materials in their original packaging until needed to prevent damage.
   - Confirm that all required components are present and in good condition.
   - Examine any pre-installed parts and re-tighten connections as necessary to ensure stability and safety.

3. **Compliance and Safety Verification**
   - Review local building codes applicable in your state and local jurisdiction.
   - Before beginning construction, confirm that all necessary permits have been obtained.
   - Review operating and safety instructions for all tools to prevent accidents during construction

2. Foundation and Structural Work

Introduction

The Foundation and Structural Phase is the most critical stage of deck construction, as it establishes the load-bearing base and primary support system for the entire structure. This phase involves preparing the site, setting accurate layouts, installing footings, posts, and ledgers, and ensuring all structural connections meet local building codes. Precision at this stage guarantees stability, safety, and long-term durability.

Getting this phase right is essential for a professional-quality result. Proper alignment, moisture protection, and code compliance prevent structural failures, simplify later steps, and extend the life of your deck. Take time to verify measurements, inspect materials, and follow all guidelines—this foundation will determine the success of every subsequent phase.

Tools and Materials Required

- Concrete Deck Block (CB-026, SKU-CB-026)
- Post Anchor 4 in x 4 in (PA-003, SKU-PA-003)
- Post Anchor 6 in x 6 in (PA-004, SKU-PA-004)
- Pressure-Treated Deck Post 4 in x 4 in (DP-001, SKU-DP-001)
- Strong-Tie Joist Hanger LUS26 (JH-005, SKU-JH-005)
- Deck Joist Flashing Tape (FT-024, SKU-FT-024)
- Safety gear (gloves, safety glasses, and dust mask)
- Tape Measure
- Level
- Square
- Drill

Step-by-Step Guide

3. Deck Framing and Surface Preparation

Introduction

The Deck Framing and Surface Installation Phase focuses on creating the structural framework that supports your deck surface (the walking surface), provides structural rigidity and ensures long-term stability. This stage involves installing beams, joists, and blocking with precision to maintain proper alignment, load distribution, and compliance with building codes. Accurate framing is essential for a level deck surface and smooth installation of decking boards.

Getting this phase right is critical for both safety and aesthetics. Proper spacing, secure connections, and attention to detail prevent structural issues, minimize future maintenance, and deliver a professional-quality finish. Take time to verify measurements, fastener types, and alignment before proceeding to the decking surface installation.

Tools and Materials Required

- Pressure-Treated Wood Deck Board (DB-011, SKU-DB-011)
- Composite Deck Board – Trex Transcend (DB-009, SKU-DB-009)
- Deck Screws Composite #10 x 2.5 in (DS-013, SKU-DS-013)
- Deck Screws Stainless Steel (DS-012, SKU-DS-012)
- Hidden Fastener System – CAMO (HF-022, SKU-HF-022)
- Measuring Tape
- Level
- Square
- Drill

Step-by-Step Guide

4. Stair Construction and Installation

Introduction

Stairs are a critical functional component of a residential outdoor deck, providing safe and convenient access between different levels. This phase involves precise measurement, cutting, and assembly of stringers, treads, and risers to ensure stability, comfort, and compliance with building codes. Proper stair construction enhances usability and integrates seamlessly with the overall deck design.

Accuracy in this step is essential for safety and durability. Incorrect rise and run dimensions, poor alignment, or inadequate fastening can lead to structural failure and safety hazards. By following the recommended guidelines and verifying each measurement, you will achieve a secure, code-compliant stair system that complements your deck and stands the test of time.

Tools and Materials Required

- Deck Stair Stringer 3-Step (SS-029, SKU-SS-029)
- Deck Stair Tread Composite (ST-050, SKU-ST-050)
- Tape Measure
- Level
- Square
- Drill

Step-by-Step Guide

5. Railing and Safety Barrier Installation

Introduction

Railings and safety barriers are essential components of a residential outdoor deck, providing protection against falls and ensuring compliance with building codes. This phase focuses on installing posts, panels, and handrails with precision to create a secure and visually appealing enclosure. Proper installation enhances both safety and the overall design of your deck.

Accuracy in this step is critical for preventing hazards and achieving a professional finish. Incorrect spacing, loose connections, or inadequate height can compromise safety and fail inspection standards. By following the recommended guidelines and verifying each measurement, you will create a sturdy, code compliant railing system that safeguards your deck for years to come.

Tools and Materials Required

- Deck Railing Kit Composite (RK-017, SKU-RK-017)
- Deck Railing Kit Aluminum (RK-018, SKU-RK-018)
- Deck Post Sleeve Composite (PS-032, SKU-PS-032)
- Measuring Tape
- Level
- Square
- Drill

Step-by-Step Guide

Deck Railings & Safety Phase – Step-by-Step Guide
1 Install Railing Posts Securely
2 Attach Railing Panels or Balusters
3 Attach Railing Panels or Balusters
3 Install Post Sleeves and Caps
4 Verify Railing Height and Strength